

BOARD OF
BUILDING AND SAFETY
COMMISSIONERS

MARSHA L. BROWN
PRESIDENT

HELENA JUBANY
VICE PRESIDENT

VAN AMBATIELOS
VICTOR H. CUEVAS
ELENORE A. WILLIAMS

CITY OF LOS ANGELES
CALIFORNIA



ANTONIO R. VILLARAIGOSA
MAYOR

DEPARTMENT OF
BUILDING AND SAFETY
201 NORTH FIGUEROA STREET
LOS ANGELES, CA 90012

ROBERT R. "BUD" OVROM
GENERAL MANAGER

RAYMOND S. CHAN, C.E., S.E.
EXECUTIVE OFFICER

The Steel Network, Inc.
2012 T. W. Alexander Dr.
P. O. Box 13887
Durham, NC 27709

Attn: Gary Bennett or
Kristy Andrews
(919) 845-1025

RESEARCH REPORT : RR 25631
(CSI # 05 40 00, 05 05 23)

BASED UPON ICC EVALUATION SERVICE
REPORT NO. ESR- 1903

REEVALUATION DUE
DATE: February 1, 2014
Issued Date: January 1, 2012.
Code: 2011 LABC

GENERAL APPROVAL - Reevaluation - Verticlip SL, SLB, SLS, AND SLT Exterior Curtain-Wall Steel Stud Connectors, and the Verticlip SLD Interior Head-of-Wall Steel Stud Connector.

DETAILS

The above assemblies and/or products are approved when in compliance with the description, use, identification and findings of Report No. EST-1903, Reissued June 1, 2011 of the ICC Evaluation Service, Incorporated. The report, in its entirety, is attached and made part of this general approval.

The Parts of Report No. EST-1903 marked by asterisks are modified by the Los Angeles Building Department from this approval.

The approval is subject to the following conditions:

1. Cross section, support details and connection details of each stud or joist shall be shown on plans to be reviewed by Structural Plan Check of the Department. The plans shall bear the signature of a Civil or Structural Engineer registered in California.
2. Where exposed to the weather the connectors shall be galvanized.
3. Product shall be install according to Section 4.2 of ESR-1903.
4. Wall assembly design wall shall comply with Section 2210.6 of the 2011 Los Angeles City Building Code.
5. Screws shall be in compliance with LARR.

The Steel Network, Inc.

Re: Verticlip SL, SLB, SLS, AND ALT Exterior Curtain-Wall Steel Stud Connectors and the Verticlip SLD Interior Head-of-Wall Steel Stud Connector.

6. Products shall be installed in accordance with this report.

DISCUSSION

The report is in compliance with the 2011 Los Angeles City Building Code.

The approval was based on test data complying with AC-261.

This general approval will remain effective provided the Evaluation Report is maintained valid and unrevised with the issuing organization. Any revisions to the report must be submitted to this Department, with appropriate fee, for review in order to continue the approval of the revised report.

This general approval of an equivalent alternate to the Code is only valid where an engineer and/or inspector of this Department has determined that all conditions of this approval have been met in the project in which it is to be used.

Addressee to whom this Research Report is issued is responsible for providing copies of it, complete with any attachments indicated, to architects, engineers and builders using items approved herein in design or construction which must be approved by Department of Building and Safety Engineers and Inspectors.



WILLIAM STUTSMAN, Chief
Engineering Research Section
201 N. Figueroa St., Room 880
Los Angeles, CA 90012
Phone- 213-202-9812
Fax- 213-202-9943

KH:kh
RR25631/MSWord2007
R01/11/12
2F3/2C/2210

Attachment: ICC-ES Evaluation Report No. ESR-1903 (4 pages)